

Highway Department  
FY2011 Work Plan – First Draft

Work to be scheduled as Contracted:

1. Paving 2 Miles of Whipple Hollow road starting on the south end from West Rutland town line with a ½” shim and a 1 ¼” top coat Approximant cost \$165000.00 based on \$60.00 per ton.

2. Paving Gorham Bridge road with a ½” shim and a 1 ¼” top coat Approximant cost 37,000.00 based on \$60.00 per ton.

Work to be scheduled for Highway Crew:

1. Roadside shoulder improvements Tree cutting and Cutting Banks back, Ditching; Cutting Shoulders Goat Farm, Oxbow, Furnace, Old Hubbardton, Sugar Hollow and Elm street near Cooley Bridge.

2. Replace culvert on Elm street that runs into otter creek. Will have to notify Vermont stream alteration division.

3. Cutting shoulder on Whipple Hollow for paving and putting shoulders down after paving.

Continue regular scheduled maintenance including: brush cutting; weed trimming; roadside mowing; grading and rock raking; applying calcium chloride; graveling dirt roads where needed; culvert maintenance and replacement as needed; sweeping sidewalks and roads; sign maintenance; painting stop bars on pavement; winter maintenance and equipment maintenance; Also assisting other departments as needed.